

Department	Standard Components	Room Tag:	4080
Room Name	Staff Station, 14m2	Room Code:	SSTN-14-SJ
<b>Net Room Area Briefed</b>	14.0 M2		
<b>No of Rooms</b>	1		
<b>Subtotal of Briefed Area</b>	14.00 M2		
<b>Hours of Operation</b>	24 Hours		
<b>Occupancy</b>	Up to 3 staff		
<b>Also covers these Rooms</b>			
<b>Description/ Special Requirements</b>	<p>The Staff Station is the administrative base for a Unit, and enquiry point for patients and visitors. It provides for the co-ordination of patient care, observation, writing up of clinical notes, entering data into computers and making and receiving telephone calls. The Staff Station may also accommodate a Unit Receptionist/ Clerk. The floor area may vary according to the Unit, activity level, number of full and part-time staff, the Operational Model and the building layout. The Staff Station 14m2 is suitable for a typical Inpatient Unit of 30 beds.</p> <p>Acoustics: Sound attenuation level - Medium; acoustic privacy required.</p> <p>Special Design Requirements:</p> <ul style="list-style-type: none"> <li>- Staff Station should have a set down area for disabled access</li> <li>- Lockable counter height doors may be provided for additional security if required.</li> </ul>		
<b>Amendment</b>	13.03.2014 - First Issue		

### Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
5007	Ceiling	Plasterboard	Paint	Bulkhead		optional
6025	Cornice	Aluminium	Powdercoat	shadow line		
9050	Doors	Laminate	Prefinished	Single leaf, counter height		920mm clear opening, lockable, optional for security
9002	Doors	Solid Core/ Glass	Paint	Single leaf, half glazed		920mm clear opening, optional to adjoining Office-Clinical/Write-up
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		carpet also acceptable
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		or timber skirting over carpet
3000	Wall finish	Paint	Acrylic, washable			
4050	Wall protection	Timber/MDF	Stain/ clear finish	Combined rail and crash bar at 900AFFL		to front of desk, optional

Department | Standard Components  
 Room Name | Staff Station, 14m2

Room Tag: 4080  
 Room Code: SSTN-14-SJ

**Fittings and Furniture (FF)**

ID	Description	Category	Group	Qty	Selection / Remarks
2100	Chair: ergonomic, office	Furniture/ Fitting	3	3	
4230	Counter top	Furniture/ Fitting	1	1	resinate or laminate, to staff station
11465	Keyboard shelf: drop down	Furniture/ Fitting	1	2	optional
17255	Pedestal filing unit: mobile, 660mmH	Furniture/ Fitting	3	2	under bench, lockable
17360	Pinboard: fabric covered	Furniture/ Fitting	1	1	to upstand of staff station
21250	Staff station: laminate/ timber	Furniture/ Fitting	1	1	with low section for wheelchair visitors
24100	Waste bin: paper, 20 Litre	Furniture/ Fitting	3	1	under bench

**Fixtures, Equipment and associated Services (FE)**

ID	Description	Group	Qty	Ele	Data	Cd	W	H	T	W	/m	WTap	Dns	Gas	Selection / Remarks
11400	Computer: PC & monitor	3	2	yes	yes	___	___	___	___	___	___	___	___	___	
54510	Telephone: handset, standard	3	2	___	yes	___	___	___	___	___	___	___	___	___	
68700	Xray viewer: 2 screen	1	1	yes	___	___	___	___	___	___	___	___	___	___	recessed

**Services**

ID	Description	Service Category	Qty	Selection / Remarks
1006	Voice / Data outlet: double	Communications	2	1 outlet on each panel for telephone
5000	Airconditioning	HVAC		
5070	Temperature control	HVAC	1	control panel, optional
6000	General fluorescent	Lighting		
6030	Special: downlights	Lighting		dimnable for night lighting
6055	Special: task light, built in	Lighting		under countertop
7050	Gas Alarm Panel	Medical Gases	1	as required
8040	Annunciator	Nurse Call	1	
9001	GPO: Double	Power	4	
9060	GPO: Special: for equipment	Power	1	X-ray viewer
10005	Duress alarm	Security	1	